

WAIOHINE-MANGATARERE RIVER SCHEME

SCHEDULE OF FLOOD DAMAGE – FEBRUARY 2004

Site	Damage	Repair Work	Cost	Priority
Druzianic/Herrick /Bicknell	Channel alignment	Clear re-align channel	\$4000	High
Bicknell	Tree slumping	Willow clumps	\$4500	High
Wong	Boulder rip-rap	Supply and place additional rip-rap	\$7000	High
Saywell	Tree slumping	Clumps	\$3000	High
Ticehurst	Alignment	Extend rock groynes	\$10000	High
Clarke	Alignment	Concrete block groynes	\$4000	High
Brazendale	Alignment	Channel alignment	\$2000	High
Bassett	Alignment	Channel alignment	\$2000	High
Platform Farm	Alignment	Channel alignment	\$1500	High
Halliday	Alignment	Rock groynes	\$10000	High
Fairbrother	Alignment	Extend rock groynes & channel alignment	\$12500	High
Playle	Alignment	Channel alignment	\$1500	High
Vandenbosch	Bank, alignment	Repair bank, channel alignment	\$3000	High
Mangatarere				
Quinn	Edge slumping	Willow clumps	\$6000	High
Tucker	Edge slumping	Willow clumps	\$5000	High
McLennan	Edge slumping	Willow clumps	\$4000	High
		SUB TOTAL	\$80,000	