

UpperRuamahanga
Flood Damage ScheduleMt Bruce Scheme
February 2004

Site	Damage	Repair	Cost(\$)	Priority	
Ravenstone	Bank erosion 180m	Channel alignment/shingle groynes Planting	12000 2000	M M	
Edwards	Bank erosion 25m	*Willow cabling	2000	M	H - High
Van Barnveld	Bank erosion 120m	*Willow clumps Channel alignment	6000 3000	M H	M - Medium
Graham Stuart	Bank erosion 150m with threat of river course change	Major channel realignment Willow clumps *Widening of the narrow section	15000 7000 25000	H H H	
Duncan Stuart	Bank erosion 100m with threat of river course change	Channel realignment Willow clumps	16000 8000	H M	
Duncan Stuart	Bank erosion 40m	*Willow cabling	2000	M	
McLachlan	Bank erosion	Channel alignment *Rail groynes/Willow clumps	6000 7000	M M	
Te Ore Ore "Crusher"	Bank erosion	*Willow clumps	7000	M	
		Total	118000		
		Amount to be accommodated in the current years programme	16000		
		*Items programmed for the next financial year	49000		
		Net amount	53,000		