

UpperRuamahanga
Flood Damage ScheduleTe Ore Ore Scheme
February 2004

Site	Damage	Repair	Cost(\$)	Priority	
Forbes	Bank erosion 80m	Major Channel alignment	28000	H	
		*Willow clumps	12000	M	
Oliver	Bank erosion 40m	*Willow cabling	6000	H	H - High
		Clear scrub from opposite berm	3000	M	
River road	Bank erosion 20m	*Willow cabling	2000	M	M - Medium
Percy	Damage to boulder/rock groynes and bank erosion	Repair groynes	12000	M	
ditto		*Willow cabling	6000	M	
Holmes/Wardells	Damage to boulder/rock groynes and bank erosion	Repair groynes	12000	M	
ditto		Willow cabling/clumps	11000	M	
Oxidation Ponds	Damage to rock groynes	Repair groynes	18000	H	
Total			110000		
Amount to be absorbed in to the current years programme			28000		
*Items programmed for the next financial year			26000		
Net amount			56,000		